

# Introduction of Jplanning Guam Corporation (DBA) West Pacific Concrete





株式会社 Jplanning



## Concrete stirring drum

### MODEL S PAVING CONFIGURATION

**Productivity:** Pre-blending of materials increases production rates. Configured for high-production dump on grade applications, the plant produces up to 35 loads per hour. With the addition of the Horizontal Mixer Option the plant will produce up to 55 loads per hour.

**Versatility:** With the Ready Mix Conversion option, the RexCon Model S will tackle the many different daily mix designs in your job rack. Central Batching is the optimal plant for controlling slump for bridge, curb, median barrier, RCC, high-performance, and high slump structural concrete, among other quality-monitored mixes.

**Economy:** A central mix plant will produce more ready mix concrete consistently through improved uniformity, slump control, and faster truck loading times. Optimized material usage helps to meet your energy goals.



### Standard Plant Specifications

**Tilt Mixer Trailer:** 12 yd<sup>3</sup> / 9.2 m<sup>3</sup> (CPMB) tilt mixer with poly-lined drum, 30HP hydraulic pack, emergency mixer tilting, and mixer stand

**Plant Base Trailer:** 12 yd<sup>3</sup> / 9.2 m<sup>3</sup> (CPMB) aggregate batcher with 35,000lb / 22,679 kg load cells, 48" / 122 cm wide batch belt (500 FPM / 152.4 MPM), 20 HP air compressor with 120 gal. / 454.2L tank, 4.6 HP aeration blower.

**Cement Trailer:** 600 bbl / 112.7 ton split 1/3, 2/3 compartment silo with double wall, high and low bin signals, mixer charging hood, five 5" cement fill pipes, gravity batched water holding reservoir, 12 yd<sup>3</sup> / 9.2m<sup>3</sup> (CPMB) cement batcher with 10,000 lb / 4,536 kg load cells

**Aggregate Bin Trailer:** 90 yd<sup>3</sup> / 135 ton (CPMB) reversible three compartment

**Controls / Electrical System:** RexCon RC3 computer batch controls & 460 volt power panel with starters



DUMP CONE AND MIXER MAINTENANCE PLATFORM

#### Ready Mix Application Options

- 205 Ton Aggregate Bin & Turnhead
- Mixer Maintenance Platform
- 750 BBL Cement Silo
- Telescopic Boot
- Central Dust Collector & Shroud



PRE-BLENDED MATERIAL



It is uniformly stirred by this drum  
(Quality assurance)





## Water purifier



Water of constant quality is supplied by the water purification device.  
(Imported from Japan)



株式会社 Jplanning



## State of pre-shipment inspection



Samples are taken and inspected before shipment,  
Confirm whether it is as specified by customer or not

According to law, if it is over a certain load capacity,  
Use auxiliary wheels so as not to damage the road.  
WEST PACIFIC CONCRETE complies with the law





## House used container



The control room (overall process control room)  
and the office building,  
Use all containers

Office

Control room